Attention to the students who will make 1st submission of the highway assignment!

In the list below, there are possible mistakes that may be done in the preparation of the highway assignment.

- Please be careful to not make mistakes given in this list, while preparing your homework.
- The evaluation of the assignment will be made according to these mistakes. So, please try to do not these mistakes.

Mistake No	Explanation
Mistake No 1	Coordinates were not adjusted according to the student ID.
Mistake No 2	Information in the title block is missing or incorrect.
Mistake No 3	The scale of the temporary plan is incorrect.
Mistake No 4	There was no zero line or it was invisible.
Mistake No 5	Zero line intervals were not equal.
Mistake No 6	Zero line intersected with contour line (or these are tangent) and zero line was not divided to the small part.
Mistake No 7	Zero line was not drawn by dashed line.
Mistake No 8	The slope of the zero line was not written.
Mistake No 9	The route was not close to the zero line and earthwork was not balanced.
Mistake No 10	The distance between the inverse curves was below the minimum value (60 m).
Mistake No 11	The distance between the curves with the same direction was below the minimum value (30 m).
Mistake No 12	Curve radius was selected as less than 100 m, not suitable (if it is not a necessity)
Mistake No 13	Curve radius was not selected as a multiple of 5.
Mistake No 14	The distance between consecutive cross-sections was less than 5m or more than 25m (max 20m in curved section).
Mistake No 15	The beginning or ending points of the curves is coincided with the cross-section A or C.
Mistake No 16	Values of the curve elements were incorrect or missing.
Mistake No 17	Curve elements were calculated but not written on the outside of the curve on the plan.
Mistake No 18	The amount of cross-sections was not sufficient in order to define ground line.
Mistake No 19	Cross-section widths were not as much as right of way.
Mistake No 20	According to the direction of road (from A to C), cross sections names were not written to the left or km values to the right.
Mistake No 21	Cross-sections were not placed perpendicular to the centerline of the road.
Mistake No 22	Platform lines were drawn in temporary plan.
Mistake No 23	The scale of the temporary profile is incorrect.
Mistake No 24	The longitudinal slope was not written on the profile
Mistake No 25	There are missing sections in the table given at the bottom of the profile.
Mistake No 26	Points A and C were not connected by a red line on the profile.
Mistake No 27	The distribution of earthworks was not balanced.
Mistake No 28	The temporary plan sheet was not submitted.
Mistake No 29	The temporary profile sheet was not submitted.
Mistake No 30	Other